KADUR DIVISION.

Dated 31st May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 25th June 1929, 3 P.M., for constructing a new dispensary at Javali, Mudgere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed within four months from the date of acceptance of tender.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 400 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for constructing a new dispensary at Javali, Mudgere Taluk " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Shimoga, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimated amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after the acceptance of tenders.

11. Rates should be quoted for each item of work and lumpsum rates are subject to modification as per data worked out during execution.

Approximate estimate of quantities for the construction of a New Dispensary at Javali Mudgere Taluk.

No.	Items of work	Per	Quantity
	I. *Main Building Dispensary.*		
1	Earthwork excavation for foundation and filling in basement	C.yd.	70
2	Stone jelly concrete for foundation	C.ft.	997
3	Burnt stone in mortar for foundation and basement ...	,,	1,286
4	Burnt brick in mortar	,,	1,836
5	Burnt stone slabs 6" thick dressed	Sq.ft.	265
6	Teakwood panelled doors with hinges 3 tower bolts, locking arrangements and hinged stoppers, etc., complete.	,,	182
7	Teakwood windows half panelled and half glazed shutters with ¾" iron bars, hinged stoppers hinged hooks, rings, etc., complete.	,,	120
8	Teakwood gate for verandah with iron works, etc., complete ...	,,	20
9	Honnewood work wrought and put up	C.ft.	102·61
10	Roofing with First Class Mangalore tiles on teak reepers ...	Sqr.	13·85
11	Ridge tiles set in mortar and cement pointed ...	Rg.ft.	103
12	Chunnam plastering	Sqr.	35·48
13	White and colour washing with 2 coats	,,	35·48
14	Ornamental eve board	Rg.ft.	136
15	Chacolate painting outside and woodoiling inside with two coats.	Sqr.	3·42
16	Woodoiling with two coats	,,	6·42
17	Constructing V shaped drain with stone jelly cement concrete and plastering with cement.	Rg.ft.	30
18	Providing glass tiles	,,	10
19	Providing surki 3'x3'x1' with burnt stone slabs laid on 3" concrete bed and cement plastered.	No.	3
20	Flooring with Mangalore 9" sq. tiles on 3" concrete bed and cement pointing	Sqr.	6·17

No.	Items of work	Per	Quantity
21	Cadappa slab flooring on 3" concrete bed and cement pointing.	Sqr.	1·44
22	Providing teakwood cup-board with pegs, etc., complete ...	Rg.ft.	100
23	Parapet wall with chunam plastering	C.ft.	54
24	Cement pointing to basement	Sqr.	2·50
25	Clearing site and levelling ground and forming approach roads.	Lump	sum
	II. *Kitchen attached to Dispensary.*		
1	Earthwork excavation and filling in basement including watering and tamping.	C.yd.	7
2	Stone jelly concrete in mortar	C.ft.	48
3	Size burnt stone in mortar	,,	115
4	Burnt brick in mortar	,,	291
5	Burnt stone slabs 6" thick dressed	Sq.ft.	19
6	Honnewood work wrought and put up including tarring the imbedded portion.	C.ft.	12·75
7	Teakwood door with battened shutters, hinges, bolts, etc., complete.	Sq.ft.	18
8	Do windows with battened shutters iron bars, bolts, etc., complete.	,,	9
9	Roofing with First Class Mangalore tiles on teak reepers 2"x 1" and nailing, etc., complete.	Sqr.	2·40
10	Ridge tiles set in mortar and cement pointing ...	Rg.ft.	15
11	Flooring with First Class Mangalore tiles 9" sq. on 3" concrete bed and cement pointing.	Sqrs.	0·70
12	Plastering with mortar	,,	5·26
13	White washing and colour washing with 2 coats ...	,,	5·26
14	Chacolate painting to doors, windows and eve boards ...	,,	1·01
15	Providing plane teakwood eve board	Rg.ft.	30
16	Providing teakwood large boards	,,	32
17	Constructing an oven	Lump	sum
18	Providing mortar and pestle	Lump	sum
19	Do sink	Lump	sum
	III. *Latrine attached to Dispensary.*		
1	Earthwork excavation	C.yd.	8
2	Filling the foundation with stone jelly concrete in mortar ...	C.ft.	80
3	Burnt stone in mortar	,	88
4	Burnt brick in mortar	,,	153
5	Constructing seats	...	...
6	Constructing cement concrete bed of drain with cement plastering.	Lump	sum
7	Plastering with mortar	Sqrs.	4·39
8	Concrete flooring with plastering and cement rendering inside	,,	0·50
9	Coping with burnt brick in mortar including plastering (1 1/8 x $\frac{3}{4}$').	Rg.ft.	40
10	Tarring to the height of 3'	Sqr.	1
11	White and colour washing with 2 coats	,,	4·39

Dated 31*st May* 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 25th June 1929, till 3 P.M., for raising the waste weir crest of Indavara Huligunda Tank, Reg. No. 203 of Chikmagalur Taluk An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chikmagalur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 175 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for raising the waste weir of Indavara Huligunda Tank," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimated amount will not be accepted.

10. No claims for enhanced rates rates will be entertained on any account after the acceptance of tenders.

11. Rates should be quoted for each item of work and lumpsum rates are subject to modification as per data worked out during execution.

Detailed estimate for raising the waste weir of Indavara Huligunda Tank, Chikmagalur Taluk, Registered No. 203, Major Tank.

Particulars of work	Quantity	Per	Rate	
			In figures	In words
1. Earthwork to bund watering and tamping ...	7,502	C.yd.		
(a) Do above, saturation line 2' high in rear of bund.	11,356	,,		
2. Cutting grips in bund	4,501	S.yd.		
3. New stone work with jelly backing and wedging	112	C.yd.		
4. Jungle clearing, removing roots, etc. ...	L. S.	...		
5. Removing and refixing Grade, Index, Register No. and B. M. Stones.	10	No.		
Waste Weir R. *L.* 103·0C, *Length* 42, *Crest width* 3 *feet.*				
1. Earthwork excavation chargeable to bund ...	...	...		
2. Concrete stone jelly in mortar	189	C.ft.		
3. Burnt brick in surki mortar	1,630	,,		
4. Plastering with surki mortar	11·39	Sqr.		
5. Removing, cutting and refixing old burnt stone slab in surki mortar.	326	S.ft.		
6. Burnt stone slabs new to body wall set in surki mortar.	14	,,		
7. Cement pointing to coping slabs	3·40	Sqr.		
8. Unforeseen items	L. S.	...		

B. KRISHNA RAO,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

Attention is invited to the publication notified in the *Mysore Gazette*, Part VI, pages 471 to 477, dated 23rd May 1929, tenders for constructing Dalvoy tank near Singadahalli, Chiknayakanhalli Taluk.

Last date for presentation of the tender is 12th June 1929 up to 2 P.M.

V. V. PATANKAR,
Executive Engineer.